

## APPENDIX B

### Toronto and Region Conservation Authority Stormwater Management Criteria and Requirements

#### Quantity Control

- 2-100 Post to Pre-development for sites with drainage areas less than 5 hectares.
- Don River Unit Release Rates for drainage areas greater than 5 hectares.

#### Quality Control

- Enhanced Level (80 % Total Suspended Solid Removal).

#### Erosion Control

- For a 25 mm event, it must be released over 48 hours for sites greater than 5 hectares.

#### Water Balance

- Detain a rainfall depth of 5 mm from all impervious areas.



Young + Wright / IBI Group Architects

