



Welcome to the Public Open House for The City of Vaughan Stormwater Management Ponds Site 13, Site 18 & 22, and Site 20

Project Objective

- City applied for partial funding from the federal Disaster Mitigation Adaption Fund (DMAF) in 2019
- 2009 SWM Retrofit Study by Aquafor identified locations with the potential to improve water quality, erosion and flooding
- The partial funding will be used to add/improve stormwater management infrastructure at key locations surrounding Rainbow Creek and Robinson Creek
- Proposed infrastructure updates will:
 - Improve storm runoff water quality
 - Improve flood protection

Locations

Retrofit Site 13 from an existing dry pond facility to a wet pond




Locations

- Construct a new wet pond facility at Site 20 from an existing uncontrolled storm outfall
- Construct a new wet pond facility at Site 18 + Site 22 from existing uncontrolled storm outfalls




Existing Conditions – Site 13




Proposed Works – Site 13

ARMOURSTONE RETAINING WALL




HICKENBOTTOM OUTLET

Existing Conditions – Site 18 & 22




Proposed Works – Site 18 & 22




Existing Conditions – Site 20



Proposed Works – Site 20



Tennis Court Relocation and Renewal



Proposed Tennis Court Location



Proposed Bridge Replacement Locations





Design Elements

- Basic Design Elements
 - Excavation
 - Plantings
 - Armourstone Retaining Walls
 - Sewer Realignment
 - Operation and Maintenance Features
 - Access Roads
 - New Outlets/Channel



- Noise, Dust, Mud, Vibrations
- Total truckloads: 200-300 trucks per day during peak hauling times (6-8 weeks, intermittent)
- Working Hours: M-F, 7am-7pm
- Pre-construction Inspections of Homes:
 - Third Party inspection of home exterior and interior.
 - Used to confirm if possible damage is cause by construction (i.e. vibration)
 - Inspections are completed as permitted by homeowner
 - Completed for homes within close proximity to site.
- Closures to trails and sidewalks
- Tree Removals



Site 13 – Wet Pond

Access/Working Limits

- Main Truck Access from Martin Grove Road
- Site Access via Martin Grove Road and Triton Ave
- Construction limited to site area



Site 18 & 22 – Wet Pond

Access/Working Limits

- Main Truck Access from Woodbridge Ave
- Site Access via Moonstone Place
- Hwy 7 to Woodbridge via Kipling Ave
- Construction limited to site area



Site 20 – Wet Pond

Access/Working Limits

- Main Truck Access from Hwy 7 and Kipling Ave
- Site Access via Highway 7
- Construction limited to site area



Finished Work

- Open Waterbody
- Enhanced Trees/Landscaping
- Decorative Armourstone Wall
- New Hickenbottom Outlet and Spillway
- Access Road
- Pedestrian Trail





Project Duration

- General Construction Timing
 - Late Fall 2023 December 2024
 - Estimated to take 12-14 months to complete
- Closer to Construction:
 - City to provide updated notification on start dates for each area
 - Newsletter will be delivered to citizens in the vicinity of the construction and posted to City website

Project Contacts

Alan Manlucu, P.Eng

Project Manager

City of Vaughan 2141 Major Mackenzie Dr. Vaughan, ON L6A 1T1

D. (905) 832-8585 ext. 8468

E. Alan.manlucu@vaughan.ca



Will Cowlin. P.Eng.

Project Engineer

Aquafor Beech Ltd. 2600 Skymark Ave, Bldg 6, Suite 202 Mississauga, Ontario L4W 5B2

D (519) 803-7834 E cowlin.w@aquaforbeech.com

