COMMUNICATION: C1

VMC S-C MEETING : February 13, 2018

ITEM:1



Edgeley Pond + ParkVMC Sub-Committee


February 13, 2018



Presentation Overview

- 1. Site context and background
- 2. Design evolution
- 3. Funding allocation and Phase 1 construction cost
- 4. Next steps






Site Photos




Storm water Functionality

Current limits of Regulatory Floodplain

- Hydrologic and hydraulic simulations based on current Humber River watershed models for existing and future land use
- Additional consideration for future climate variability simulated by increasing flow rates by 20%






Municipal Class EA
November 2012



BCFS Preliminary Design January 2015



BCFS Preliminary Design January 2015



Black Creek Financial Strategy
May 2016



BCFS Preliminary Design January 2015



Edgeley Pond and Park June 2017

EPP Master Plan

June, 2017

Design elements:

- Reduce flood risk with a comprehensive and balanced SWM system
- Re-establish Black Creek watercourse
- Celebrate innovative SWM by creating a functional, recreational and natural pond
- Preserve natural heritage
- Increase ecological net benefit
- Create iconic landforms and a memorable space
- Integrate site edges with proposed residential development
- Activate Jane Street frontage
- Expand passive recreation trail network
- Integrate informal amphitheater
- Include a flexible lawn area at south edge






Design Process and Site Investigations

	BCFS Preliminary Design (2015)	EPP Detailed Design (2017)
Conceptual Design 3rd Party Costing Public & Stakeholder Process Stormwater Modeling Natural Heritage Systems Report Site Investigation - Geotechnical ESA Studies	✓	* * * * * * * * * * * * * * * * * * *







Stormwater

 Traditional use of forebay on the west and settlement tank and polishing pond on the east

Black Creek Restoration

- No geomorphological studies
- Creek varies from 2.5 4.5m wide

Ecological Enhancements

· Design was completed with out site investigation

Public Space

- SWM 'lake' was the focus of the site (30cm deep)
- East and west sides of park connected through table land bridges, not in the valley

Maintenance + Lifecycle Cost

- Restricted maintenance access with size of waterbody - challenging post flood cleanup
- Large settlement tank and polishing pond maintenance
- · Traditional forebay maintenance

Construction + Costing

- High level costing done by TMIG + Schollen
- · Construction period unknown

BCFS Preliminary Design

January 2015

Stormwater

· OGS's and bioswales

Black Creek Restoration

- · Geomorphological studies included
- · Creek varies from 7.2 8.4m wide

Ecological Enhancements

 Natural Heritage Systems Report identified value in the island and informed the planting plan

Public Space

Looped valley and table land pathways are accessible from multiple points

Maintenance + Lifecycle Cost

- Street side OGS's
- Bioswales will require maintenance similar to forebay's (reduced footprint)
- Large control structure wall

Construction + Costing


- Class C costing done by third party cost consultant
- Geotechnical investigation informed drawings and cost estimate.
- 2-year construction period anticipated

Edgeley Pond and Park

June 2017

Preliminary Overall Budget Comparison

Project Main Components	Project Budget based on BCFS	EPP 60% Cost Estimate (after Value Engineering)	Difference Between Estimates
Culvert Works (N-E Corner of Hwy 7 and Jane	\$5.3M	\$4.97M	\$0.33M
Edgeley Pond Civil Works	\$9.0M	\$15.6M	-\$6.6M
Edgeley Pond Enhanced Design Components	\$6.1M	\$3.2M	\$3.1M
Overall Budget Comparison	\$20.4M	\$23.8M	\$3.4M
		LESS CWWF GRANT	\$2.5M
	TOTAL ADDITIO	NAL FUNDING REQUIRED	Approx. \$1.0 M



Black Creek Financial Strategy Funding Allocation

Black Creek Financial Strategy

Depending on the Functional Benefits of each component of the project, a relevant funding source(s) was assigned:

For Example, a road crossing would benefit:

- Flood Control
- Transportation
- Open Space Network

Costs were apportioned over the funding sources

Road crossing / creek / culvert



Preliminary Budget Comparison Based on BCFS

Project Main Components	BCFS Allocated Funds	EPP 60% Cost Estimate (after Value Engineering)	Difference Between Estimates	Cost Increase on a Component Basis
Culvert Works (N-E Corner of Hwy 7 and Jane	\$5.3M	\$4.97M	\$0.33M	\$
Edgeley Pond Civil Works	\$9.0M	\$15.6M	-\$6.6M	-\$6.6M
Edgeley Pond Enhanced Design Components	\$6.1M	\$3.2M	\$3.1M	\$
	\$20.4M	\$23.8M		\$6.6M
			LESS CWWF GRANT	\$2.5M
	TOTAL ADD	DITIONAL FUNDING REQ	UIRED (\$6.6M – \$2.5M)	Approx. \$4.1M

Edgeley Pond and Park - Civil Works Components

COMPONENTS Culvert Works (north of Hwy 7)	BCFS 2015 \$5,314,000	EPP 60% DD \$4,970,000	Cost Increase
Earthworks, Erosion, Sediment Control, Site Prep	\$3,414,000	\$3,710,000	- \$296,000
Natural Channel Realignment and Restoration	\$1,038,000	\$1,560,000	- \$522,000
Plant Material	\$1,490,000	\$2,345,000	- \$855,000
Main Control Structure	\$844,000	\$1,865,000	- \$1,020,000 Essential flood control
Oil Grit Separators, East Inlet Wall, Flow Disperser, Concrete Pipes	\$754,000	\$2,195,000	- \$1,440,000 works
Pond & Creek Edge Treatments	\$1,332,000	\$3,190,000	- \$1,860,000
Urban Design Features	\$127,000	\$127,000	
Other works including electrical		\$650,000	- \$650,000

Next Steps

- Advance detailed design to 90%
- Complete the contractor pre-qualification process in March
- Report to the FAA Committee in April 2018 with the project budget assessment and amendment request with consideration for the Clean Water and Wastewater Fund (CWWF) grant funding of \$2.47 million awarded to this project
- Continue to pursue the necessary permits and approvals
- Prepare tender documentation by the end of May 2018
- Report to VMC Sub-Committee in June 2018 with a project update and details on the final project design, tendering and construction schedule

EDGELEY POND AND PARK PROJECT - VMC

